BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 68

Name of Work:-Providing street lights and Ornamental lights in Attur ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri . ANITHA S T	
				Rate	Rate in Words
1 P.No 22 I.No4.16	Supplying High pressure sodium vapour street light luminaire suitable for use with high pressure sodium vapour lamp with integrated control gear and grey colr powder coated. The fitting shall be non corrosive pressure die cast aluminium housing with high purity anodized aluminium housing with EPDM Gaskets suitable for Outer Dia of pole 40 mm -60 mm. Cable entry through a cable gland with toggle clips. IP65 protection for both optical & electrical compartment. Bottom cover may be with poly carbonate/tempered/ toughened glass.Luminaire efficiency should be > 60 % and ambient temperature >35 deg C. High Intensity Discharge electro magnetic ballast with copper winding of Orthccyclic winding coil. Class H insulated dual coated copper wire. Complaince to IEC 61347-2-9 Safety & IEC 60923-Performance. Winding Temperature rise " T=70 deg C. Luminaire shall be suitable to operate on 230/250 V 50 Hz AC supply finish including wiring , Ignitor, condenser, SS Toggles for opening front hingeable glass 250 Wattsa) Group 'A'	Each	62	5900.00	Rupees five thousand nine hundred only
2 P.No-108 I.No-17.1.2	Supplying & fixing of 32 mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 or rail or RCC pole/wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires complete. Using 32mm dia G.I pipe	Each	62	750.00	Rupees seven hundred fifty only
3 P.No-15 I.No-3.3.1	Supplying and Fixing of Bakelite D.P/Socket/Switch with /Without neon indicator over existing wood board or flush mounting in plastic plates/nitches, as per IS 1293 and IS 3854 Using Group A material 32 Amps Flush/ projected type DP Switch	Each	50	125.00	Rupees one hundred twenty five only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri . ANITHA S T	
				Rate	Rate in Words
4 P.No-3 I.No-1.6.4	Supplying and flush mounting teak wooden box without front plant made of not less than 12mm thick wood, after due groove cutting, finishing with necessary cement plastering complete.8"X6"X3"	Each	50	40.00	Rupees forty only
5 P.No-12 I.No-2.12.1	Wiring for lighting/power circuit using one of PVC insulated 1100v grade stranded Aluminium unsheathed wire single core/multi core cable in open or consealed system of wiring.as per IS-694:1990 4 sqmm	mtr	500	5.00	Rupees five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.